

APPROVED TENDER SCHEDULE - 'B'


Item No: 16

Name of Work:-Improvements to roads and drains at Chikkabommasandra main and cross roads in ward no 04

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri BHASKAR K	
			Rate	Rate in Words
KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift up to 1.5m,excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no142, PWD SR 2016-17)	Cum	415.20	91.01	Rupees Ninety One and Paise One Only
KSRB 100-1 Loading and unloading of stone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumping turning for return trip excluding time for haulage and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 cost of haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 134 (SR 2016-17)	Cum	415.20	103.87	Rupees One Hundred Three and Paise Eighty Seven Only
KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)/ PWD SR 2016-17	Cum	26.10	5401.49	Rupees Five Thousand Four Hundred One and Paise Forty Nine Only
4 Providing and laying Plain /reinforced cement concrete for side drains wall and bottom thickness 15cm using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc.completeexcluding cost of steel as per MORTH specification No.1500,1700,2200 Page No 265 lte mo 37.59.2 SR 2016-17	Cum	61.07	11551.01	Rupees Eleven Thousand Five Hundred Fifty One and Paise One Only

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri BHASKAR K	
			Rate	Rate in Words
KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46/ PWD SR 2016-17	Quintal	40.31	6747.71	Rupees Six Thousand Seven Hundred Forty Seven and Paise Seventy One Only
RCC Precast covering slab for drain (10cm thick)	Sqm	88.50	2198.70	Rupees Two Thousand One Hundred Ninety Eight and Paise Seventy Only
Providing precast slab of 250 mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge-	Sqm	8.10	5351.22	Rupees Five Thousand Three Hundred Fifty One and Paise Twenty Two Only

K. Bhaskar
Signature of the Contractor


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.